




UPPSALA
UNIVERSITET



Experiences from the series double-spoke cavity cryomodules for ESS

Akira Miyazaki on behalf of FREIA team

Uppsala University

TESLA TECHNOLOGY
TTC
COLLABORATION

TTC2022






The FREIA team: international experts from different fields





European Spallation Source for science with neutrons


Courtesy C. Maiano



Assembly at Orsay → Assessment at Uppsala → Installation at Lund



@IJCLab
Orsay



@FREIA
Uppsala




@FREIA
Uppsala



@ESS
Lund


ESS double-spoke cavity cryomodule (x13+1)



parameter	value
f [MHz]	352.210
β_{opt}	0.50
E_{acc} [MV/m]	9.0
$B_{\text{pk}}/E_{\text{acc}}$ (B_{pk})	6.8 (61 mT)
$E_{\text{pk}}/E_{\text{acc}}$ (E_{pk})	4.3 (38 MV/m)
G [Ω]	133
R/Q [Ω]	427
L_{acc} [m]	0.639
Q_{ext}	1.75-2.85e5
BW [kHz]	1.2-2.0
Q_0	>1.5e9


Operation parameters

- 90 MeV \rightarrow 216 MeV
- Peak current 62.5 mA
- Bunch length 2.86 ns
- RF pulse length 3.2 ns
- Repetition rate 14 Hz
- RF duty cycle 4.5 %
- Temperature 2K
- Max RF power 335 kW



- **ESS offers the first deployment of double-spoke cavities** (difference from SNS)
- Practical challenges beyond mere R&D in the laboratory

ESS spoke cavity modules at FREIA: progress and planning



	qualified	Disqualified by FREIA	To be tested
Qualification in the 1 st test	6 (CM05, CM01, CM06, CM07, CM08, CM11)	5 (CM02, CM04, CM03, CM09, CM10)	3 (CM12, CM13, CM14)
Qualification in the 2 nd test	3 (CM02, CM04, CM03)	0	2 (CM09, CM10)

More than two years nonstop during Covid-19


Issue in welder → fixed

	No problem	Found by IJCLab	Found by FREIA	To be tested
Vacuum leak in SCHe double-wall tube of a coupler	8 (CM02, CM05, CM01, CM06, CM07, CM08, CM10, CM11)	1 (CM03)	2 (CM04, CM09)	3 (CM12, CM13, CM14)
Stepper motor issue	8 (CM05, CM06, CM01, CM07, CM08, CM09, CM11, CM12)	0	4 (CM02, CM03, CM04, CM10)	2 (CM13, CM14)




Lessons learned & Performance statistics

Warm RF coupler conditioning



Preconditioning at IJCLab




Travelling wave up to 400 kW
in a dedicated test bench


Lesson learned

- Out-gassing is below 100 kW (multipacting barrier)
- Travelling wave conditioning before assembly was not enough
- 24h x 3-4 days up to duty cycle 4.5%
- Stability of the RF system for 24 hours is crucial

Conditioning at FREIA




(ESS CM05)




Standing wave up to 400 kW in
a cryomodule (off resonance)


2nd conditioning (i.e. commissioning)




(CM02 2nd)



After 2 months in static
vacuum at warm





Warm coupler conditioning summary




CM	FPC1	FPC2	times	# of stations	# of pumps	Live time [hours]
CM02 1 st	CPL01	CPL04	1 st	2	1	112
CM04 1 st	CPL11	CPL03	1 st	2	1	67
CM02 2 nd	CPL01	CPL04	2 nd	2	2	9
CM05	CPL14	CPL18	1 st	2	2	66
CM03 1 st	CPL06	CPL26	1 st	2	1	109
CM01	CPL10	CPL12	1 st	2	2	90
CM04 2 nd	CPL32	CPL05	1 st	1	2	147
CM03 2 nd	CPL06	CPL26	2 nd	2	2	12
CM06	CPL11	CPL20	1 st	2	2	66
CM07	CPL25	CPL30	1 st	2	2	48
CM08	CPL21	CPL15	1 st	2	2	65
CM09	CPL27	CPL28	1 st	2	2	30
CM10	CPL23	CPL24	1 st	2	2	10
CM11	CPL22	CPL19	1 st	2	2	26
CM12	CPL03	CPL09	1 st	2	2	92


- Huge variation from 10 h to 92 h even with the same condition
- More active pumping during assembly reduces the necessary conditioning time (cf SPIRAL2)
- Residual Gas Analysis indicates peak at 15 amu and 28 amu which are typical sign of CH (cf plasma processing)




Local thermal quench at very low field (< 1 MV/m)



CAV IN




CAV OUT




Local quench & thermal feedback is almost always observed at very low field in the spoke cryomodules so far → special care (interlock) is mandatory

Accelerating gradient and field emission



- All the cavities reached the nominal gradient 9 MV/m
- Some cavities showed field emission but probably safe (→ next slide)


Uncertainty in the field calibration (Q_t)




- Q_t from Vertical Test generally **underestimates** the field value
- Error estimation in Q_t in CM is 10% mainly from power calibration's uncertainty
 - Stored energy estimated from the integral of decaying reflected power

Static and RF heat loads

- The temperature of the thermal screen is 80 K while the one in ESS is 40 K
 - Our static heat load is just a reference
- Gas helium flow in the exhaust line has been used to estimate the heat load
 - LHe level drop and pressurizing in closed volume have been taken as spare data
- Averaged static heat load is 16.5 W for each module
 - Thermo-acoustic oscillation has been observed in some cases in the prototype valve box
- Averaged total heat load (9 MV/m for both cavities) is 17.4 W for each module
- RF power dissipation (<2 W) is almost always within fluctuation of helium gas flow (1-2 W) for heat load estimation
 - This is because Q_0 is above spec and duty cycle is only 4.5%




Q_{ext} and required forward power for a given I_b



$$P_f = \frac{V_{acc}^2}{4 \frac{R}{Q} Q_{ext}} \left\{ \left[1 + \frac{I_b \frac{R}{Q} Q_{ext}}{V_{acc}} \cos \phi_s \right]^2 + \left[\frac{2Q_{ext} \delta \omega_m}{\omega} \right]^2 \right\}$$


$V_{acc} = 9 \text{ MV/m} \times 630 \text{ mm} = 5.75 \text{ MV}$
 $R/Q = 427 \Omega, I_b = 62.5 \text{ mA}, \phi_s = 20^\circ$




- Statistically distributed around the lower edge of the spec.
 - A few cavities were even out of spec
- Less margin in forward power in linac
- Option: in the earlier stage of the section with lower E_{acc}
- Is it critical or not → closed loop operation with LLRF + piezo

Frequency tuning


Frequency shift from 300 K to 2K



Frequency sensitivity to pressure






Tuning range vs tuning length




- The frequency tuning is under control
- Mechanical stress might be a problem in the future project and discussions are on-going with MINERVA

Dynamic Lorentz force detuning vs piezo tuning range




- Piezo tuning range was with unipolar bias (0-200V) in quasi-static condition slower than 50V/1min
- LFD < piezo tuning range is generally applied and active piezo compensation would be feasible
- Simultaneous operation of two piezos or use one a spare


Field emission and thermal cycles (CM11)




- Several thermal cycles dramatically mitigated a strong field emission
 - The beam vacuum was never vented
 - Nothing except for the tuner was moved
 - The residual gas analysis indicates outgassing of 15 amu (CH_4) and could be a sign of CH removal (?)
- Plasma processing in spoke cavities may give us some hints in this phenomena




1st warming up



2nd warming up



3rd warming up








Conclusion

- FREIA laboratory in Uppsala University is in charge of qualification of series spoke-cavity cryomodules for ESS in collaboration with IJCLab
- 9 modules have been qualified and 5 modules will be tested by March 2023
- Lessons learned
 - Coupler conditioning in CM can take time but its duration has been statistically very different
 - Thermal quench happens at very low field and interlock setup is crucial even at very low field
 - All the cavities so far reached the spec (9 MV/m) with some disagreement of field calibration between vertical tests and high-power cryomodule tests
 - Field emission was observed in some of the cavities but may not be critical for the machine
 - External Q of couplers are statistically at the lower edge of the spec for unknown reason
 - The thermal screen temperature is different from ESS and static heat load may not be relevant
 - RF heat dissipation is so small that precise measurement seems not feasible
 - Coarse tuning was under control and piezos can compensate Lorentz force detuning
- Some speculations about field emission and potential CH contamination
 - This may motivate plasma processing studies in spoke cavities

backup

Challenges in cryomodules: complicated integration



FREIA is leading **low- β cryomodule** assessment in Europe

Standard test of one spoke-cavity module

week	1st week											
day	MON		TUE		WED		THU		FRI		SAT	SUN
	m	a	m	a	m	a	m	a	m	a		
activity	departure from Orsay		transport				reception		reception test			

week	2st week											
day	MON		TUE		WED		THU		FRI		SAT	SUN
	m	a	m	a	m	a	m	a	m	a		
activity	doorknob mounting	installed in bunker		cryogenic connection		vacuum connection		RF calibration at warm		pumping		

week	3rd week											
day	MON		TUE		WED		THU		FRI		SAT	SUN
	m	a	m	a	m	a	m	a	m	a		
activity	coupler warm conditioning							LN shield cooling				

week	4th week											
day	MON		TUE		WED		THU		FRI		SAT	SUN
	m	a	m	a	m	a	m	a	m	a		
activity	cooling down to 4K	4 K filling	thermalization	2K pumping	multipacting conditioning	CTS test						
	f vs T measurement	coupler cold conditioning		f vs p								calibration at cold

week	5th week											
day	MON		TUE		WED		THU		FRI		SAT	SUN
	m	a	m	a	m	a	m	a	m	a		
activity	heat load measurement	start warming up		warming up				warming up completed				

week	6th week											
day	MON		TUE		WED		THU		FRI		SAT	SUN
	m	a	m	a	m	a	m	a	m	a		
activity	out from bunker	dismount doorknob, dry N2		out going test		departure		arrival at ESS		TTC2022		

Legend	
	Mechanical work
	RF coupler conditioning
	Cold test

Main part of the test takes 4 weeks

Enevitabile 18 days

- Pumping 3 days
- Coupler conditioning 24h x 3-4 days
- Thermalization 7 days for CTS
- Warming up 4 days

Mechanical work takes more than 1 week but **overlap** with other modules help

The closed loop operation of LLRF is not included in the plan and was not tested except for the prototype module because

- Fully functional LLRF has not been ready
- Simply no time to fit the 4-weeks plan (additional one week must be considered)