

# Present status of RIKEN power coupler


OZEKI, Kazutaka

RIKEN Nishina Center, Wako, Japan




# Overview of SRILAC


## Superconducting Riken Heavy Linear Accelerator



- Installed at downstream of existing RILAC.
- 10 SC-QWRs are mounted in three CMs.




# History of CMs and FPCs




*Machine availability and reliability in SRILAC at RIKEN  
K. Yamada, Oct. 12 16:00~*

2019	Mar. Sep.~	<p>Assembly and installation of CMs.</p> <p>Evacuation of QWRs and CMs, cool-down test of CMs.</p> <p>Nov. 17: Vacuum leakage from a FPC window.</p>
2020	Jan. Jun.~	<p>1<sup>st</sup> beam acceleration test.</p> <p>Beam delivery to experiments.</p> <p>Oct. 27: Vacuum leakage from another FPC window.</p>
	Dec.	Redesign and production of new FPCs.
2021	May Aug. Sep.	<p>Installation of outer windows to SC05 and SC06.</p> <p>Delivery of four new FPCs.</p> <p>Installation of outer windows to remaining eight FPCs.</p>
2022	Nov.	Six new FPCs will be delivered.

# Vacuum leakage from FPC windows



2019	Mar. Sep.~	Assembly and installation of CMs. Evacuation of QWRs and CMs, cool-down test of CMs. <b>Nov. 17: Vacuum leakage from a FPC window.</b>
2020	Jan. Jun.~	1 <sup>st</sup> beam acceleration test. Beam delivery to experiments. <b>Oct. 27: Vacuum leakage from another FPC window.</b>
	Dec.	Redesign and production of new FPCs.
2021	May Aug. Sep.	Installation of outer windows to SC05 and SC06. Delivery of four new FPCs. Installation of outer windows to remaining eight FPCs.
2022	Nov.	Six new FPCs will be delivered.



## Most probable process to vacuum leakage:

Dew condensation on air-side of vacuum window




Galvanic corrosion of metallization of alumina




Degradation of brazing of vacuum window


# Outer windows



2019	Mar.	Assembly and installation of CMs.
	Sep.~	Evacuation of QWRs and CMs, cool-down test of CMs. Nov. 17: Vacuum leakage from a FPC window.
2020	Jan.	1 <sup>st</sup> beam acceleration test.
	Jun.~	Beam delivery to experiments. Oct. 27: Vacuum leakage from another FPC window.
	Dec.	Redesign and production of new FPCs.
2021	May	Installation of outer windows to SC05 and SC06.
	Aug.	Delivery of four new FPCs.
	Sep.	Installation of outer windows to remaining eight FPCs.
2022	Nov.	Six new FPCs will be delivered.



# Redesign of new FPCs



## Components to be replaced:

- Inner conductor
- Vacuum window
- Lower part of outer conductor

- Higher thermal conduction at lower part of outer conductor.


	Material of outer conductor below Vac. Win.	Estimated Temp. at vacuum window (Assumed Temp. of lower end of IC and OC are both 300 K)
Present FPCs	SS + Cu-plating	~283 K
New FPCs	<b>Thick copper</b>	~298 K

- Installation of heater around vacuum window.

2019	Mar. Sep.~	Assembly and installation of CMs. Evacuation of QWRs and CMs, cool-down test of CMs. Nov. 17: Vacuum leakage from a FPC window.
2020	Jan. Jun.~	1 <sup>st</sup> beam acceleration test. Beam delivery to experiments. Oct. 27: Vacuum leakage from another FPC window.
	Dec.	<b>Redesign and production of new FPCs.</b>
2021	May Aug. Sep.	Installation of outer windows to SC05 and SC06. Delivery of four new FPCs. Installation of outer windows to remaining eight FPCs.
2022	Nov.	Six new FPCs will be delivered.

# Pre-processing of new FPCs

2019	Mar.	Assembly and installation of CMs.
	Sep.~	Evacuation of QWRs and CMs, cool-down test of CMs. Nov. 17: Vacuum leakage from a FPC window.
2020	Jan.	1 <sup>st</sup> beam acceleration test.
	Jun.~	Beam delivery to experiments. Oct. 27: Vacuum leakage from another FPC window.
	Dec.	Redesign and production of new FPCs.
2021	May	Installation of outer windows to SC05 and SC06.
	Aug.	<b>Delivery of four new FPCs.</b>
	Sep.	Installation of outer windows to remaining eight FPCs.
2022	Nov.	Six new FPCs will be delivered.



Outer conductor: SS + Cu-plating


Vacuum window

Outer conductor: Thick copper

## Pre-processing in ISO class-1 clean room:


- Particle removal (blow only)
  - Installation to RF test chamber
  - Evacuation
  - Baking (2 days)
  - RF process (w/ outer window)
  - Sealing w/ dry N<sub>2</sub>
- } Outgas measurement

# Outgas measurement (1)




RGA  
PrismaPro QMG 250 (Pfeiffer Vacuum)

Mass distributions of residual gas  
at each step



# Outgas measurement (2)


Outgas induced by baking



- $M = 1, 17, 18$  increased by baking.

# Outgas measurement (3)



Outgas induced by RF process



- $M = 2, 17, 18$  gradually increased by RF supply.  
(continued to increase even if RF wasn't supplied.)
- $M = 2, 18, 28, 44$  largely increased by multipacting.


# Outgas measurement (4)

Another example of outgas induced by multipacting





# Preparation for replacement of FPCs (1)

Floor plan around SRILAC



(radiation management issues)



CM2

Wall

~310 mm

Hard to move CMs to other clean place → On-site replacement of FPCs


- Clean environment under CM
- FPC elevating device
- Full-scale model of lower part of CM  
→ Simulate FPC replacement process in advance.

Under consideration

# Preparation for replacement of FPCs (2)


## Plan for clean booth under CM

- Vinyl chloride film enclosing whole area under CM
- Clean air-flow from upstream and down stream of CM




# Preparation for replacement of FPCs (3)

## Plan for FPC elevating device



## Plan for full-scale model of CM




Aluminum frame (MISUMI Corp.),  
Aluminum plate, etc....

# Preparation for replacement of FPCs (4)

## Test: Cleanliness of fan filter unit

Simple  
clean booth



AIRTECH JAPAN, LTD.  
Stainless steel fan filter unit  
EC-MAC (equivalent to SS-MAC)  
ULPA filter

Obstacle

Bell-mouth of  
particle counter



LASAIR III 100  
(Particle Measuring System)

(Outside of clean booth: ISO class 4)




Clean booth (Plastic curtains)	Number of $\geq 0.1 \mu\text{m}$ particles measured [counts/s]
Closed	ND
Open	< 10 (ISO class ~ 3 ?)

A system to enclose additional fan filter unit and FPC may be needed.

# Preparation for replacement of FPCs (5)

## Test: Dust emission from linear bushing

FPC elevating device



Bell-mouth of particle counter

(Similar FPC elevating device)


Ball screw  
BSSC2005 (MISUMI Corp.)  
enclosed with poly bag.

No dust emission while raising and lowering FPC table.


Linear bushing LHFRF (MISUMI Corp.)  
w/o low dusting grease

## Test: Rotation of ball screw under load

FPC table (with new FPC on it) was raised to the top of shaft.



After 3 days  
➔



No rotation



# Summary

---

- In RIKEN, CM operation started from Sep. 2019.
- Since then, vacuum leakages from FPC window occurred twice.
  - May be due to dew condensation at air side of vacuum window.
- Outer windows were installed to all 10 FPCs
  - for provision and prevention to the vacuum leakage.
- New FPCs were redesigned and are now being produced.
  - Improve thermal conduction at lower part of outer conductor.
- Four new FPCs were already delivered and pre-processed.
  - RGA was introduced to measure outgas during pre-processing.
- Preparation for replacement of FPCs are now under progress.
  - Clean environment under CM.
  - FPC elevating device.
  - Simulation of FPC replacement process.


Replacement of FPCs: After present experiment ?

(Super-heavy element synthesis experiment has been ongoing since Jun. 2020.)




# Estimation of temperature distribution

Present FPC



New FPC



# Outgas induced by multipacting

All detected masses are plotted.

